

WHITMAN COUNTY PUBLIC WORKS
P.O. Box 430
310 North Main Street
Colfax, WA 99111

Solid Waste Division, David Nails, Director, (509) 334-2400 for questions or access for inspection.

REQUEST FOR VENDOR QUOTE

SPECIFICATIONS:

Whitman County is requesting vendor quotes from Qualified Contractors to install closed cell foam 2" R-14 (such as Gaco Western 1850 2# closed Cell foam 2" R-14, or equal) underside spray foam insulation to the inside of our 94' X 122' transfer station metal roof at the Carothers Road Solid Waste Facility.

The Contractor's work is required to be complete no later than 5 calendar days after Notice to Proceed.

Bidders are encouraged to visit the project site to become familiar with the existing site conditions and the general elements of the project. All work shall come with a 1-year warranty.

The Contractor is responsible for:

- Coordinating with the Owner all work at the facility. Providing submittals of all work products, construction quality control, and demonstrating performance with the requirements of the specifications.
- Obtaining all necessary permits.
- Employing necessary safety precautions throughout project execution.
- Supplying all equipment to execute and perform the job.
- Supplying all of the materials to execute and perform the job.
- Cleaning up after the project is complete. Including any overspray onto electrical conduit or lights.
- Project to conform to prevailing wage laws of Washington State.
- Maintain general liability insurance on all vehicles.
- Must be a Washington State Licensed Contractor.
- Cover all spray applied insulation with fireproofing or retardant in accordance with, building codes & manufacturer's recommendations (which might include intumescent paint or other products).

BASIS OF AWARD:

All materials, equipment and labor	\$ _____
Subtotal (before tax) (Basis of Award)	\$ _____
Sales Tax 7.8%	\$ _____
Project Total	\$ _____

Date:

Company:

Address:

Phone:

Fax:

Email:

Signature:

Title:
